

SECTION 1

PRELIMINARIES

SPECIAL NOTES

- 1** The Contractor is required to check the numbers of the pages and should any be found to be missing or in duplicate or the figures or writing indistinct, they must inform the Quantity Surveyors at once and have the same rectified. Should the Contractor be in doubt about the precise meaning of any item, word or figure, for any reason whatsoever, or observe any apparent omission of words or figures they must inform the Quantity Surveyor in order that the correct meaning may be decided upon before the date for the submission of the Tender.
- 2** No liability whatever will be admitted nor claim allowed in respect of errors in the Contractor's Tender due to mistakes in the Bills of Quantities which should have been rectified in the manner described above.
- 3** Any doubt or obscurity as to the meaning or intention of any part of the tender documents, or any question arising, shall be taken up in writing, before submission of the tender so that the same can be clarified.
- 4** The Contractor shall not alter or otherwise qualify the text of these Bills of Quantities. Any alteration or qualification made without authority will be ignored and the text of the Bills of Quantities as printed will be adhered to.
- 5** The Contractor shall be deemed to have made allowance in their prices generally to cover items of Preliminaries or additions to Prime Cost Sums or other items, if these have not been priced against the respective items.
- 6** All items of measured work shall be priced in detail and tenders containing lump sums to cover trades or groups of work must be broken down to show prices for each item before they will be accepted. Lump sums to cover items of Preliminaries shall likewise be broken down if so required.
- 7** In no case will any expenses incurred by Contractors in preparation of this Tender be reimbursed.
- 8** The copyright of these Bills of Quantities is vested in the Quantity Surveyors and no part thereof may be reproduced without their express permission given in writing.
- 9** The Contractor is solely responsible for the accurate ordering of materials in accordance with the Drawings and Architect's instructions and no claims for any loss or expense will be entertained for orders for materials based upon the Bills of Quantities.
- 10** The Bills of Quantities must be priced in US Dollar currency, i.e. US Dollars and Cents.
- 11** The tender documents must be priced in ink.

INDEX

SECTION NO. 1	PRELIMINARIES AND GENERAL DESCRIPTIONS
SECTION NO. 2	PITCH
SECTION NO. 3	SPECTATOR STANDS
SECTION NO. 4	FENCE WALL
SECTION NO. 5	GRAND SUMMARY

ITEM	DESCRIPTION	AMOUNT (US\$)
	<p>SECTION NO. 1</p> <p>PRELIMINARIES AND GENERAL DESCRIPTIONS</p> <p>PRELIMINARY PARTICULARS</p> <p>A PARTIES</p> <p>The "Employer" is INTERNATIONAL ORGANIZATION FOR MIGRATION</p> <p>For the purpose of the works which are under the control of the consultants above, the respective consultants shall be deemed to be invested with the duties and be representatives of the Architect.</p> <p>B SITE</p> <p>The site is located on LUUQ DISTRICT</p> <p>The site of the works shall be used solely for the purpose of executing and completing the Contract to the satisfaction of the Architect.</p> <p>The Contractor shall obtain the Architect's approval for the siting of all temporary storage areas for materials.</p> <p>The Contractors shall visit the site to acquaint themselves with its nature and position, the nature of the ground, sub- strata and other local conditions, position of power and water supplies, access roads or any other limitations, and no claims for extras will be considered on account of lack of knowledge in this respect.</p> <p>The Contractor's attention is drawn to the fact that they shall confine themselves to the area necessary for executing the works as instructed by the Architect.</p> <p>The contractor must obtain the Architect's approval and directions regarding the use of any materials found on the Site. Any such material utilized in the execution of the Contract shall be measured and value assessed by the Quantity Surveyor and the amount credited to the Employer.</p> <p style="text-align: center;">Carried To Collection</p> <p>GENERAL MATTERS</p>	<p style="text-align: right;">US\$</p>

A SUFFICIENCY OF TENDER

The Contractor shall be deemed to have satisfied themselves before tendering as to the correctness and sufficiency of their Tender for the Works and of the rates and prices stated in the priced Bills of Quantities, which rates and prices shall cover all their obligations under the Contract and all matters and things necessary for the proper completion and maintenance of the Works.

B STAMP CHARGES

The Contractor shall allow for the payment of all Stamp Charges in connection with the Surety Bond and Contract Agreement.

C DEFINITIONS AND ABBREVIATIONS

Terms used in these Bills of Quantities shall be interpreted as follows:

- "Approved" shall mean approved by the Architect.
- "as directed" shall mean as directed by the Architect or any other consultant in the contract.
- "BS" Shall mean the current British Standard Specification published by the British Standards Institution, 2 Park Street, London W.1, England.
- "CM" shall mean Cubic Meters.
- "SM" shall mean Square Meters.
- "LM" shall mean Linear Meters.
- "mm" shall mean Millimeters.
- "Kg" shall mean Kilograms.
- "No." shall mean Number.
- "m.s" shall mean Measured separately.
- "Ditto " shall mean as described before or as above described.

D PROGRESS SCHEDULE

The Contractor shall, upon receiving instructions to proceed with the work, draw up a Time and Progress Schedule setting out the order in which the Works are to be carried out with the appropriate dates thereof. This Time and Progress Schedule is to be agreed with the Architect and no deviation from the order set out in this Schedule will be permitted without the written consent of the Architect. The Main Contractor will be responsible for arranging the above programme with all Sub-Contractors including the Nominated Sub-Contractors and Nominated Suppliers.

E FIGURED DIMENSIONS

Figured dimensions are to be followed in preference to dimensions scaled from the Drawings; but whenever possible dimensions are to be taken on the Site or from the Buildings. Before any work is commenced by Sub-Contractors or Specialist Firms, dimensions must be checked on the Site and/or buildings and agreed with the Contractor, irrespective of the comparable dimensions shown on the Drawings. The Contractor shall be responsible for the accuracy of such dimensions.

Carried To Collection

US\$

A PROVISIONAL WORK

All "provisional" and other work liable to adjustment under this Contract shall be left uncovered for a reasonable time to allow all measurements needed for such adjustment to be taken by the Quantity Surveyor. Immediately the work is ready for measurement, the Contractor shall give notice to the Quantity Surveyor.

If the Contractor makes default in these respects he shall, if the Architect so directs, uncover the work at his own expense to enable the measurements to be taken.

B EXISTING SERVICES

Prior to commencement of any work the Contractor is to ascertain from the relevant Authorities the exact position, depth and level of all existing electric cables, water pipes or other services in the area and they shall make whatever provisions may be required by the Authorities concerned for the support and protection of such services. Any damage or disturbance caused to any services shall be reported immediately to the Architect and the relevant Authority and shall be made good to their satisfaction at the Contractor's expense.

C TRANSPORT TO AND FROM THE SITE

The Contractor shall include in their prices for the transport of materials, workmen, etc., to and from the Site of the proposed Works, at such hours and by such routes as are permitted by the Authorities.

D OVERTIME

The Contractor shall allow in their tender for any extra costs for overtime working they consider will be necessary in order to complete the works by the contract Date of Completion.

If during the course of the Contract overtime is worked for a specific purpose in accordance with a written instruction issued by the Architect, the Contractor will be reimbursed in respect of such overtime to the extent only of the additional net cost of unproductive time payable over and above the basic hourly rates as laid down by the Regulations of Wages and Conditions of Employment Act, Building and Construction Industry Wages council and excluding any bonuses, profits and overheads.

E PUBLIC AND PRIVATE ROADS, PAVEMENTS, ETC.

The Contractor will be required to make good, at their own expense, any damage they may cause to the present road surfaces and pavements within or beyond the boundary of the Site, during the period of the Works. In particular, all existing trees, shrubs, plants, etc., which may be destroyed or damaged during the progress of the Works are to be made good by the Contractor to the approval of the Architect.

F POLICE REGULATIONS

The Contractor is to allow for complying with all instructions and regulations of the Police Authorities.

Carried To Collection

US\$

A CONTRACTORS' SUPERINTENDENCE

The Contractor shall constantly keep on the Works a literate English-speaking Agent or Representative, competent and experienced in the kind of work involved, who shall give his whole time to the superintendence of the Works. Such Agent or Representative shall receive on behalf of the Contractor, directions and instructions from the Architect and such directions and instructions shall be deemed given to the Contractor in accordance with the Conditions of Contract. The Agent shall not be replaced without the specific approval of the Architect.

It is to be a specific condition of this Contract that the successful Tenderer shall provide on site throughout the period from the completion of the substructure to the Date for Practical Completion a suitably qualified, experienced and competent person to ensure that the works are carried out to the standard required by the specification and detailed on the Drawings; and shall ensure that upon any termination of employment a suitable replacement is found.

Before the Tenderer's offer is accepted the Architect will personally interview the Contractor's proposed Representative. A curriculum vitae of past experience and qualifications must be

provided for the Architect's scrutiny.

The Architect's decision will be final regarding the suitability of the proposed Representative.

B WATER

All water shall be fresh, clean and pure, free from earthy vegetable or organic matter, acid or alkaline substance in solution or suspension.

The Contractor shall provide at their own risk and cost all water for use in connection with the Works (including the work of Sub-Contractors). The Contractor shall provide at their own expense all temporary distribution pipes, storage tanks, meters, etc., and they shall clear away same upon completion of the Works.

C LIGHTING AND POWER

The Contractor shall provide at their own risk and cost all artificial lighting and power for use on the Works, including all Sub-Contractors' and Specialists' requirements and including all temporary connections, wiring, fittings, etc., and clearing away on completion. The Contractor shall pay all fees and obtain all permits in connection therewith.

D SAFETY

In particular there shall be proper provision of planked footways and guard-rails to scaffolding, etc.; protection against falling materials and tools and the Site shall be kept tidy and clear of dangerous rubbish.

The Architect shall be empowered to suspend work on the Site should he consider these conditions are not being observed, and no claim arising from such a suspension will be allowed.

Carried To Collection

US\$

A PROTECTIVE CLOTHING

The Contractor shall provide all protective or any other special clothing or equipment for their employees that may be necessary.

These shall include, inter-alia, safety helmets, gloves, goggles, earmuffs, gumboots, steel toed boots, overalls, etc according to the type of work. The Contractor shall ensure that all safety and protective gear are worn by all staff on site at all times

MATERIALS AND WORKMANSHIP

B GENERALLY

All materials shall be new unless otherwise directed or permitted by the Architect and in all cases where the quality of goods or materials is not described or otherwise specified, is to be the best quality obtainable in the ordinary meaning of the word "best" and not merely a trade signification of that word.

All materials and workmanship shall, unless otherwise specified or described, conform to the appropriate Kenya Bureau of Standards or British Standards Institution Specification current at the date of tender.

The Contractor shall order all materials to be obtained from overseas immediately after the Contract is signed and shall also order materials to be obtained from local sources as early as necessary to ensure that such materials are on Site when required for use in the Works.

The Contractor shall be responsible for and shall replace or make good at their own expense any materials lost or damaged.

The Works throughout shall be executed by skilled workmen well versed in their respective trades.

C REJECTED WORKMANSHIP OR MATERIALS

Any workmanship or materials not complying with the specific requirements or approved samples or which have been damaged, contaminated or have deteriorated, must immediately be removed from the Site and replaced at the Contractor's expense, as required.

D PROPRIETARY MATERIALS

Where proprietary materials are specified herein-after the Contractor may propose the use of materials of other manufacture but equal quality for approval by the Architect.

All materials and goods, where specified to be obtained from a particular manufacturer or supplier are to be used or fixed strictly in accordance with their instructions.

E SAMPLES

The Contractor shall furnish at the earliest possible opportunity before work commences and at his own cost, any samples of materials or workman-ship that may be called for by the Architect for his approval or rejection, and any further samples in the case of rejection until such samples are approved by the Architect and such samples, when approved, shall be the minimum standard for the work to which they apply.

Carried To Collection

US\$

A CONCRETE TESTS

Concrete test cubes I.e. per set of three as later described, including testing fees, labour and materials, making moulds, transport and handling etc.. and ensuing copies of tests are promptly dispatched to the Architect's and Quantity Surveyor's offices.
Successful tests only (Provisional)

TEMPORARY WORKS

B SPACE AND SERVICES FOR THE ARCHITECT

The Contractor shall provide where directed within the site, site offices and clean toilet facilities for the sole use of the Architect and their representatives to the satisfaction of the Local Authorities. The offices shall be provided with adequate furniture and the contractor shall provide the services of a sweeper, pay all charges and keep the facilities in a clean and sanitary condition during the whole period of the Works. In particular, the Contractor is to note that the station will continue with operations during the period of the works and a separate office and store shall be provided for full time use by the station dealer. Equally, separate sanitary amenities shall be provided for the station staff to the satisfaction of the Architect and local authorities.

C TELEPHONE

The Contractor shall provide a telephone connection to the town exchange for the period of the Works, and shall pay all fees and rental for the same. The telephone connection shall remain on site until completion of the works.

D SANITATION

The Contractor shall make arrangements for the necessary toilet facilities for their staff and workmen to the requirements and satisfaction of the Health authorities and maintain the same in a thoroughly clean and sanitary condition and pay all conservancy fees during the period of the Works and remove when no longer required.

E PLANT, TOOLS AND SCAFFOLDING

The Contractor shall provide all necessary hoists, tackle, plant, vehicles, tools and appliances of on every description for the due and satisfactory completion of the Works and shall remove same completion.

The Contractor shall provide, erect and maintain all temporary scaffolding, sufficiently strong and efficient for the due performance of the Works, including Sub-contract Works, provide special scaffolding as and when required during the Works and remove on completion and make good.

Such scaffolding shall be constructed of tubular steel or timber of sufficient scantlings and be provided with planked footways and guard-rails to approval.

All such plant, tools and scaffolding shall comply with all regulations whether general or local, in force throughout the period of the Contract and shall be altered or adapted during the Contract as may be necessary to comply with any amendments in or additions to such regulations.

Scaffolding is not measured hereinafter, and the Contractor must allow here or in his rates for the above.

Carried To Collection

US\$

A EXISTING AND ADJACENT PROPERTY

The Contractor must take all steps necessary to safeguard existing and adjacent property, make good at their own expense any damage to persons or property caused thereon, and hold the Employer indemnified against any such claim arising.

The Contractor will be held fully responsible for the safety of the existing and adjacent buildings and for any damage caused in consequence of these Works. They must reinstate all damages at his own expense and indemnify the Employer against any loss.

The Contractor must take such steps and exercise such care and diligence as to minimize nuisance from dust, noise or any other cause to the occupiers of the existing and adjacent property.

B HOARDING

The Contractor shall enclose the site areas under which work is carried out, with 1.80 meter high barbed wire fence comprising treated blue gum poles at centres not exceeding 3.0meters and 6No barbed wire strands at equal spacing

The contractors attention is drawn to the fact that some areas of the site are already built up and shall be in use during the currency of this project. As such the contractor must allow for keeping his/her employees from interfering with such other users and preventing and minimizing any nuisance arising from dust, noise or by way of trespass.

Allow for Provisional length of 100 meters @ _____ (tenderer to insert rate and extend)

B WATCHING AND LIGHTING

The Contractor shall provide at their risk and cost all watching and lighting as necessary to safeguard the Works, plant and materials against damage and theft.

C SIGNBOARD

The Signboard and lettering on same for the display of the General and Sub-Contractors' names shall be of an approved size with the Employer's name painted thereon. The Architect's Quantity Surveyor's and other Consultants' names shall be printed in 50 mm letters all to the Architect's approved design. No other signboard or advertising will be permitted without prior permission from the Architect.

Carried To Collection

US\$

A PRIME COST RATES

Where description of items include a P.C. rate per unit this rate is to cover the net supply cost of the unit only. The Contractor's price must include for the cost of the unit at the rate stated, plus waste, taking delivery, storage, fixing in position, profit and overheads.

The actual net cost per unit will be adjusted within the Final Account against the P.C. rate stated.

PROTECTION AND CLEANING

B PROTECTION

The Contractor shall cover up and protect from damage, including damage from inclement weather, all finished work and unfixed materials, including that of Sub-Contractors, etc., to the satisfaction of the Architect until the completion of the Contract.

C CLEANING

The Contractor shall, upon completion of the Works, at their own expense, remove and clear away all surplus excavated materials, plant, rubbish and unused materials and shall leave the whole of the Site and Works in a clean and tidy state to the satisfaction of the Architect, including clearing away and making good all traces of temporary access roads, offices, sheds, camps, etc. Particular care shall be taken to leave clean all floors and windows and to remove all paint and cement stains. They shall also, at the discretion of the Architect, remove all rubbish and dirt as it accumulates. The Contractor is to find their own dump and shall pay all charges in connection therewith.

Carried To Collection

US\$

Collection

Brought forward from Page	1/4
Brought forward from Page	1/5
Brought forward from Page	1/6
Brought forward from Page	1/7
Brought forward from Page	1/8
Brought forward from Page	1/9
Brought forward from Page	1/10
Brought forward from Page	1/11

TOTAL FOR SECTION 1: PRELIMINARIES AND GENERAL

US\$

Item	Description of Work/Items	Project Schedules Ref.	Unit	Qntty	Rate	Amount
	GRANT No. KIS065					
	PROPOSED LUUQ FOOTBALL FIELD					
	LUUQ, GEDO SOMALIA					
	ELEMENT 2: FOOTBALL PITCH					
	SUB STRUCTURES					
	Earthwork schedules					
A	Allow for grading of the existing surface of the pitch including clearing, importing of suitable materials for section with depressions and compact to engineer's satisfaction		Item	1.00		
B	Provision of approved painting to pitch marking to Engineer's Approval as per drawing		Lsum	1.00		
	<u>GOAL POSTS</u>					
C	Supply and fix struts/ braces of 100mm dia. CHS section of 5mm thick, with lock on synthetic net hooks, sockets caps, and wedgets bolted throughout and painted with gloss white paint to finish; dimensios to FIFA standard and Engineers approval		No.	2.00		
	<u>CORNER DELINATORS</u>					
D	Supply corner markers for 4 sides with sockets for fitting at 4 corners of the pitch comprising grouting of 25mm dia. Pipe. dimensios to FIFA standard and Engineers approval		No.	4.00		
Total for Pich Ground- BLOCK D						

Item	Description of Work/Items	Project Schedules Ref.	Unit	Qntty	Rate	Amount
	GRANT No. KIS065					
	PROPOSED LUUQ FOOTBALL FIELD					
	LUUQ, GEDO SOMALIA					
	SECTION 3: SPECTATOR STANDS					
	SUB STRUCTURES					
	<u>Earthwork schedules</u>					
A	Excavation (any soil type) for foundation.This item includes all excavations, disposal and temporary support or shoring if needed. See drawing and schedule for details.		CM	79.00		
B	Soil backfilling on RCC strip foundation up to ground level. This includes supplying of needed materials. See drawings and schedules for levels/dimensions and details.		CM	65.00		
C	Gravel compaction, Class 2, at any places under the RCC shown under stairs/ramp. This includes supplying of needed materials. See drawing and project schedules for dimensions and details.		CM	94.00		
	<u>Concrete</u>					
	<u>Plain concrete class 15/40 OR mix (1:4:8)</u>					
D	50mm Thick blinding to strip foundations		SM	15.00		
	<u>Plain concrete class 20/40 OR mix (1:3:6)</u>					
E	200mm thick strip footing and 600mm wide		CM	10.00		
	<u>Reinforcements</u>					
	<u>High tensile, square twisted bar reinforcement to BS 4461; : including bends, hooks, tying wire, distance blocks and spacers</u>					
F	8mm Bars		LM	113.00		
G	10mm Bars		LM	75.00		
SUB-TOTAL FORWARDED TO NEXT PAGE						
SUB-TOTAL BROUGHT FROM PREVIOUS PAGE						
Item	Description of Work/Items		Unit	Qntty	Rate	Amount

	Sawn formwork to:					
H	Sides of the strip footing		LM	10.00	2.00	
	Blinding & Hardcore filling					
I	50mm Thick approved quarry dust blinding to surfaces of hardcore		SM	58.00	9.00	
	Hollow concrete walling					
J	200mm thick concrete hollow blocks walling in cement sand motar (1:3)		SM	148.00	15.00	
SUBTOTAL FOR SUBSTRUCTURES						
	SUPERSTRUCTURE - CONCRETE AND WALLING					
K	Concrete Slab/stair		CM	24.00	170.00	
	Sawn formwork to:					
L	Sides of the stairs/slab		SM	39.00	4.00	
M	4No. Concrete steps		CM	11.00	180.00	
	BRC					
N	A142 BRC Mesh as per structural drawing		SM	66.00	11.00	
SUB TOTAL FOR WALLING AND SUPERSTRUCTURE CONCRETE						
	FINISHES					
	External Wall finishes					
	<u>Cement and sand (1:4) render: on hollow block: steel trowel finished: to</u>					
O	15mm thick:concrete: externally		SM	44.00	6.00	
	<u>Prepare surfaces and apply undercoat and two finishing coats first grade emulsion paint on hollow concrete wall surfaces: to</u>					
P	Hollow concrete wall: externally		SM	44.00	5.00	
	Floor finishes					
Q	<u>Cement and sand (1:4) screed: to floors: in</u>					
R	32mm thick finished floor finish		SM	65.00	5.00	
S	Provide and construct steel structure on Over head shed shelter as per drawing		Lsum	1.00	2,400.00	
	Allow for Steel railing blustrades at the sides		Lm	4.00	60.00	
SUBTOTAL FOR FINISHES						
Item	Description of Work/Items		Unit	Qntty	Rate	Amount
Summary for Spectator Stand 1						
1	Subtotal for Sub structure					
2	Subtotal for Walling and Super Structure Concrete					
3	Subtotal for Finishes					
Total for Spectator Stand 1						
Total for Two No. Spectator Stands 2NO.						

Item	Description of Work/Items	Project Schedules Ref.	Unit	Qntty	Rate	Amount
	GRANT No. KIS065					
	PROPOSED LUUQ FOOTBALL FIELD					
	LUUQ, GEDO SOMALIA					
	SECTION 4: FENCE WALL					
	SUBSTRUCTURE AND SUPERSTRUCTURE					
C	Excavate foundation trenches, 600mm wide and 800mm deep		CM	180.96		
D	Construction of RCC Strip foundation 500mm wide and 200mm thick, reinforced with 4Y10 bars, and Y8 links @ 200mm C/C spacing.		CM	37.70		
E	Construct foundation rubble stone 500mm wide and 1000mm high, bedded and jointed with cement mortar 1:3		CM	188.50		
F	Construct 200mm thick hollow block walls bedded and jointed 1:3 cement ratio.		SM	942.50		
G	Construct 200x200mm thick RCC Columns 2500mm high, reinforced with 4Y10 bars, and Y8 links @ 200mm C/C spacing, starting from ground beam		CM	10.47		
H	Construct 200mm wide x 100mm thick RCC beam, reinforced with 4Y10 bars, and Y8 links @ 200mm C/C spacing.		CM	7.54		
I	<u>Plaster: 9mm first coat of cement/lime/sand (1:2:9); 3mm second coat of cement/lime/sand (1:1:6); steel trowelled: on masonry or concrete: to both external and internal faces</u>		SM	1,885.00		
J	<u>Prepare & apply one coat of white wash, and one coat of emulsion paint on plastered hollow block concrete surfaces: to external and internal faces</u>		SM	1,885.00		
TOTAL FOR FENCE WALL						

ITEM NO.	DESCRIPTION	PAGE	AMOUNT (US\$)
	<p><u>GRANT No. KIS065</u> <u>PROPOSED LUUO FOOTBALL FIELD</u> <u>LUUO, GEDO SOMALIA</u></p> <p><u>ELEMENT 5: GRAND SUMMARY</u></p> <p>1 SECTION 1: PRELIMINARIES AND GENERAL DESCRIPTIONS</p> <p>2 ELEMENT 2: FOOTBALL PITCH</p> <p>3 SECTION 3: SPECTATOR STANDS</p> <p>4 SECTION 4: FENCE WALL</p>		
	TOTAL AMOUNT CARRIED TO FORM OF TENDER	US\$	
	<p>SIGNED:</p> <p>(CONTRACTOR)</p> <p>Address:</p> <p>Tel No:</p> <p>Date:</p> <p>SIGNED:</p> <p>(EMPLOYER)</p> <p>Address:</p> <p>Tel No:</p> <p>Date:</p>		